

**LEGEND**

**HARDSCAPE ELEMENTS**

- 01. 1.2m-wide concrete footpath to serve as secondary entrance / connection to Eugenia Rise
- 02. 2.5m-wide concrete footpath connection to residential street / main entrance
- 03. Timber beam entrance transition
- 04. 1.2m-wide timber boardwalk (flush with play surface)
- 05. Delineating concrete edge beam, partially retaining (500mm max. height)
- 06. 1.2m-wide timber boardwalk bridge over gully

**PLAYSPACE SURFACING**

- 09. Rubber scuff mats under slides and swings
- 10. Main playspace deep bark softfall
- 11. Toddler playspace synthetic turf softfall

**PARK FURNITURE**

- 12. Timber bench seat with back support
- 13. Timber bench seat
- 14. Timber bench seat
- 15. Custom timber wrap-around bench seat with 2 no. intermittent back supports distributed

**PLAYSPACE EQUIPMENT**

- A. KOMPAN Two Towers climber + slide
- B. KOMPAN Twisted net
- C. KOMPAN Balance poles
- D. KOMPAN 5M tree climber
- E. KOMPAN Combination swing set
- F. KOMPAN Tree Castle\*
- G. KOMPAN Toddler 'Forest Bug' seesaw

**PLAYSPACE ELEMENTS**

- H. Log scramble + nets\*
- I. Balance bug + tyre trail 'flight path'
- J. Stepping tree stumps\*
- K. Rubber balance / sitting 'toadstools'

**PARK PLANTING**

- 16. Planted park perimeter
- 17. Relocated Totara from previous site works
- 18. 5 no. additional shade trees
- 19. 10 no. cabbage trees featured in Log Scramble
- 20. Lawn in picnic area

- Overland flow
- \* Customised play item

\* Items subject to availability and resource consent

New Impervious surface area	22m <sup>2</sup>
Area of earthworks	995m <sup>2</sup>
Volume of cut earthworks	145m <sup>3</sup>
Volume of fill earthworks	50m <sup>3</sup>
Volume of cut to waste	95m <sup>3</sup>



EUGENIA RISE

**R AUCKLAND COUNCIL**

This plan shall be read as part of

Resource Consent No: L4C603056 24

Sheet: 2 of 10