

Cost estimate for Macleans Park Additional Gym Equipment

GYM EQUIPMENT				
Remove existing turf and topsoil to a firm subgrade suitable for installation of base course for 2 concrete pads, supply and install Gap 40 base course to a minimum thickness of 50mm	m2	8	50.00	400.00
Supply and install 2 reinforced concrete pads, 150mm depth, exposed aggregate finish, 20MPA (refer to drawings L110, L111 and L501)	m2	8	135.00	1,080.00
Allow for installation of two gym guru fitness equipment - recumbent bike and elliptical trainer on concrete pads (refer manufacturers installation instructions)	No.	2	480.00	960.00
Clean up and tidy the site, remove all materials, machinery, buildings	LS	1	1,500.00	1,500.00
Combination overhead Press and lateral pulldown	Ea	1	5,700.00	5,700.00
Shoulder Grinder	Ea	1	5,700.00	5,700.00
				\$ 15,340.00